



A **valmont** COMPANY

15/10/2025

Structural Analysis and Design Certificate

Reference Number: SC184419 OPT

Site Pro 1 can confirm that the proposed headframe at 23.1m is structurally adequate to support the loading listed below. The proposed headframe as per drawing SP20132-H8097 is clamped to Rocla pole SR3-BM27-585.

Site Details

SAED Consultant	All Telecoms	RFNSA Number	7011007
Carrier	OPTUS	Structure Owner	Optus
Carrier's Site Name	AUSTINS FERRY	Structure owner's Site Name	AUSTINS FERRY
Carrier's Site Number	H8097	Structure owner's Site No	H8097
GDA94 Coordinates	-42.77817, 147.24512		
Site Address	2 Plan 158154 Wakehurst Rd, AUSTINS FERRY TAS 7011		

Design Documentation and Parameters

Design Drawings	SP20132-H8097 Rev 0 dated 14/10/2025
Design Standards and Site Parameters	AS/NZS 1170.0 - 2002 Structural Design Actions – General principles - Importance Level 2 AS/NZS 1170.1 - 2002 Structural Design Actions – Permanent, imposed and other actions AS/NZS 1170.2 - 2021 Structural Design Actions - Wind actions - Wind Region A4 - Regional Wind Speed 45 m/s (ARI 500 years) - Design Life 50 years - Terrain Category (T_c) 2.0 - Shielding Multiplier (M_s) 1.0 - Wind Direction Multiplier (M_d) 1.0 - Topographic Multiplier (M_t) 1.16 - Climate Change Multiplier (M_c) 1.0 - Critical Direction West AS 4100 - 2020 Steel Structures

Notes

- This certificate confirms the structural adequacy of the headframe, along with all the associated members and connections, in accordance with the referenced drawing.
- The existing monopole and foundation are excluded from this structural certificate.
- Equipment support brackets are excluded from this structural certificate.
- The host structure, all steelwork and connections are assumed to be in a good condition with no latent defects.
- Combiners and Filters to be installed behind panel antennas.
- RRUs to be mounted back-to-back or side-by-side.
- RRUs can be installed at any elevation on the RRU pipe considering maximum of 3 x RRUs at each level and maximum of 4 x RRU per mount pipe.
- It is assumed the carriers will use EWP to access the headframe and ancillaries.



A **valmont** COMPANY

Loading Arrangement

Height AGL (m)	Qty	Antenna/ Equipment type	Azimuth (TN°)	Status	Carrier
23.1	3	RRVV2VV-6533D-R8	80/200/340	New	OPTUS/ VODAFONE
24.1	3	AIR3268 (B78Y)	80/200/340	New	Optus
23.1	3	AVQL (NR35)	80/200/340	New	Vodafone
23.1	3	RRU4480	-	New	Optus
23.1	3	RRU4466	-	New	Optus
24.1	6	Future RRU	-	Reserve	Optus
24.1	3	AHPB	-	New	Vodafone
24.1	3	AHCA	-	New	Vodafone
23.1	6	AHEGG	-	New	Vodafone
23.1	3	REJ FILTER (E14V00P21)	-	New	Optus
23.1	3	COM2g (E14F06P81)	-	New	Vodafone

Analysed / Designed by:

Jasper Li
BE(Civil), ME(Civil)
Graduate Engineer
On behalf of Site Pro 1
A Valmont Company

Checked / Certified by:

Sean (Shahram)
SHERI POUR
MIEAust CPEng
3524889
RPEQ 27123

Sean (Shahram) SHERI POUR
MIEAust, CPEng 3524889,
RPEQ 27123
Senior Structural Engineer
On behalf of Site Pro 1
A Valmont Company