

GENERAL AND PRELIMINARY

- 1. THE CONTRACTOR SHALL COMPLY WITH THE REQUIREMENTS OF THE SPECIFICATIONS FOR ALL WORKS AND REQUIREMENTS UNLESS NOTED OTHERWISE.
- 2. THE CONTRACTOR OR REPRESENTATIVE SHALL BE RESPONSIBLE FOR LIAISONS WITH THE PROPERTY OWNER REGARDING CONSTRUCTION OF THE INSTALLATION. THE PROPERTY MUST REMAIN SERVICEABLE AND OPERATIONAL AT ALL TIMES UNLESS AGREED WITH THE PROPERTY OWNER.
- 3. THE CONTRACTOR SHALL CONFIRM ALL DIMENSIONS ON SITE PRIOR TO FABRICATION AND CONSTRUCTION.
- 4. REFER TO GIVEN DIMENSIONS ONLY, DRAWINGS SHOULD NOT TO BE SCALED. DIMENSIONS ARE IN MILLIMETRES UNO.
- 5. SPECIFIED PRODUCTS (OR THEIR APPROVED EQUIVALENTS) SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS.
- 6. THE CONTRACTOR SHALL USE DROP SHEETS OR ANY OTHER METHOD DEEMED NECESSARY TO PROTECT THE EXISTING BUILDING FROM DAMAGE DURING CONSTRUCTION.
- 7. NORTH POINT AS SHOWN ON DRAWINGS INDICATES MGA NORTH (GDA 94 DATUM) UNLESS NOTED OTHERWISE.
- 8. ANTENNA AZIMUTHS ARE SPECIFIED IN DEGREES REFERENCED TO TRUE NORTH (TN).
- 9. ALL LEVELS ARE EXPRESSED IN METRES TO AUSTRALIAN HEIGHT DATUM (AHD).

SET OUT

- 1. THE CONTRACTOR SHALL BE RESPONSIBLE FOR SET OUT OF THE SHELTER OR OUTDOOR UNITS IN ACCORDANCE WITH THE DESIGN INTENT AS SHOWN ON THE DRAWINGS.
- 2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR SET OUT OF THE CABLE LADDER IN ACCORDANCE WITH THE DESIGN INTENT AS SHOWN ON THE DRAWINGS.
- 3. CONCRETE WORKS TOLERANCES SHALL COMPLY WITH CLAUSE 17.5 OF AS 3600.
- 4. STRUCTURAL STEELWORK TOLERANCES SHALL COMPLY WITH CLAUSE 15.3 OF AS 4100.

USE OF OPTUS STANDARD DRAWINGS

CONSTRUCTION DETAILS ON OPTUS STANDARD DRAWINGS SHALL BE ONLY BE USED WITHIN THE SPECIFIED DESIGN CRITERIA. THE OPTUS DESIGN CONSULTANT SHALL CONFIRM APPLICABILITY TO THE SITE. THE OPTUS CONTRACTOR SHALL CONFIRM ACTUAL SITE CONDITIONS ARE SAME AS STATED ON THE STANDARD DRAWINGS REFERENCED.

STRUCTURAL STEELWORK

- 1. ALL MATERIALS AND WORKMANSHIP TO BE IN ACCORDANCE WITH AS 4100, AS 1657 AND AS/NZS 1554.1.
- 2. ALL STEELWORK SHALL BE IN ACCORDANCE WITH AS/NZS 3679.1 (GRADE 300) FOR HOT-ROLLED SECTIONS AND BARS), AS/NZS 3678 (GRADE 250) FOR HOT-ROLLED PLATES AND AS 1163 (GRADE 250 (MIN)) FOR HOLLOW SECTIONS.
- 3. THE CONTRACTOR SHALL CONFIRM ALL DIMENSIONS ON SITE PRIOR TO FABRICATION.
- 4. ALL PREFABRICATED STEELWORK SHALL BE HOT-DIP GALVANISED AFTER FABRICATION, IN ACCORDANCE WITH AS/NZS 4680. PLUG AND SEAL WATERTIGHT ANY HOLES MADE FOR GALVANISING.
- 5. THE CONTRACTOR SHALL PROVIDE ALL CLEATS AND HOLES NECESSARY FOR FIXING STEEL TO STEEL AND TIMBER TO STEEL, WHETHER OR NOT DETAILED ON THE STEELWORK DRAWINGS.
- 6. UNLESS SPECIFIED OTHERWISE, WELDS SHALL BE GENERAL PURPOSE (GP) CONTINUOUS FILLET WELDS. DEFAULT SIZE IS LESSOR OF 6mm AND THICKNESS OF THE THINNEST PART BEING JOINED. STRUCTURAL PURPOSE (SP) WELDS SHALL BE SELECTED FOR STRUCTURES SUBJECT TO FATIGUE.
- 7. ANY CUTS, HOLES AND WELDS TO EXISTING STEELWORK SHALL BE TREATED WITH 'COLD-GAL' ZINC RICH PAINT.
- 8. BOLTS NOT DESIGNATED SHALL BE GRADE 8.8 TO AS/NZS 1252 AND 'SNUG' TIGHTENED.
- 9. ALL BOLTS AND U-BOLTS SHALL BE SNUG TIGHTENED AND SECURED WITH FLAT WASHER AND SPRING WASHER (UNLESS SPECIFIED OTHERWISE).
- 10. PROVIDE APPROVED NEOPRENE (OR EQUIVALENT) WASHERS AND COLLARS AT ALL DISSIMILAR METAL INTERFACES.
- 11. ALL CHEMICAL AND MECHANICAL MASONRY ANCHORS SHALL BE STAINLESS STEEL (UNLESS SPECIFIED OTHERWISE) AND INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATION.
- 12. TWO-HOLE EARTH LUGS SHALL BE PROVIDED ON ALL MOUNTS, EXCEPT ON STEEL MONOPOLES, LATTICE TOWERS AND GUYED MASTS.

CONCRETE WORK

- 1. ALL CONCRETE WORK SHALL COMPLY WITH THE CURRENT ISSUE OF AS 3600 AND OTHER RELEVANT STANDARDS REFERENCED THEREIN.
- 2. UNLESS SPECIFIED OTHERWISE, CONCRETE MIX SHALL CONTAIN PORTLAND CEMENT TYPE GP OR GB, 20mm GRADED COARSE AGGREGATE AND ACHIEVE 80mm SLUMP AT POINT OF DELIVERY.
- 3. UNLESS SPECIFIED OTHERWISE, CONCRETE COMPRESSIVE STRENGTH AT 28 DAYS (f'c) SHALL BE 32 MPa.

- 4. SIZES OF CONCRETE ELEMENTS DO NOT INCLUDE THICKNESS OF APPLIED COATINGS. BEAM DEPTHS INCLUDES SLAB THICKNESS (IF ANY).
- 5. CONCRETE SURFACES SHALL BE CURED FOR A MINIMUM OF 7 DAYS, COMMENCING IMMEDIATELY AFTER PLACING.

MASONRY WORK

- 1. ALL MASONRY WORK SHALL CONFORM WITH THE CURRENT ISSUE OF AS 3700 AND OTHER STANDARDS REFERENCED THEREIN.
- 2. BUILD IN AS NECESSARY, LINTELS, FRAMES, BOLTS, LUGS, WALL TIES AND METALWORK.
- 3. CAREFULLY POSITION OPENINGS FOR OTHER TRADES TO ELIMINATE CUTTING.
- 4. BED JOINTS ARE TO BE 10mm THICK.
- 5. BEFORE LAYING MASONRY UNITS, ENSURE THAT THE BASE IS CLEAN AND FREE OF LAITANCE.
- 6. INSTALL WIRING FOR POWER AND OTHER CONDUITS WITHIN BLOCK CORES (WHERE APPLICABLE). DO NOT CUT CHASES IN HOLLOW BLOCKWORK.
- 7. ALL WALL INTERSECTIONS SHALL BE OF BONDED CONSTRUCTION OR TIED TO EXISTING WITH MEDIUM DUTY (MIN) TIES AT 400mm CENTRES VERTICALLY.

TIMBER WORK

- 1. ALL TIMBER WORK SHALL CONFORM WITH THE CURRENT ISSUE OF AS/NZS 1684 AND AS/NZS 1720 AND OTHER STANDARDS REFERENCED THEREIN.
- 2. MINIMUM STRENGTH GRADE SHALL BE F7, UNLESS SPECIFIED OTHERWISE.

ELECTRICAL WORK (POWER)

- 1. THE ELECTRICAL INSTALLATION SHALL COMPLY WITH THE RELEVANT CODES, STANDARDS, RULES, AND REGULATIONS OF STATUTORY AUTHORITIES. IN PARTICULAR: STATE SERVICE AND INSTALLATION RULES, AS/NZS 3000 WIRING RULES, AS3015, AS/NZS 3017 AND THE SUPPLY AUTHORITY REGULATIONS.
- 2. THE LOCATIONS AND MOUNTING HEIGHTS OF THE NEW INSTALLATION SHOWN ON THE SITE DRAWINGS IS INDICATIVE ONLY. THE FINAL LOCATIONS AND HEIGHTS SHALL BE DETERMINED ON SITE TO SUIT THE CLIENT AND THE INSTALLATION. THE CONTRACTOR SHOULD VISIT THE SITE DURING THE TENDER PERIOD TO BECOME FAMILIAR WITH THE SCOPE OF WORK.
- 3. ALL REQUIREMENTS FOR INSTALLATIONS REGARDING SUPPLY ARRANGEMENTS, PROVISION OF SERVICE CABLES AND CONSUMER MAINS AND METERING SHALL BE IN ACCORDANCE WITH AS/NZS 3000 AND RELEVANT STATE SERVICE AND INSTALLATION RULES.
- 4. A SEPARATE MEN EARTH ELECTRODE SHALL BE PROVIDED BY THE CONTRACTOR BELOW THE METER BOX AS REQUIRED.
- 5. ALL WIRING SYSTEMS SHALL BE INSTALLED AND ENCLOSED BY APPROVED METHODS WHICH WILL READILY PERMIT CABLES TO BE DRAWN IN OR REPLACED AFTER COMPLETION OF CONSTRUCTION.
- 6. CABLE MARKERS SHALL BE PROVIDED FOR UNDERGROUND WIRING FROM WITHIN THE PROPERTY BOUNDARY AND TO THE OPTUS INSTALLATION, AT THE COMMENCEMENT AND FINISH OF EACH ROUTE AND AT EACH CHANGE OF DIRECTION.
- 7. ALL EXISTING SURFACES, KERBS, GUTTERS, INVERTS, VEHICLE CROSSINGS AND PAVEMENTS DISTURBED AFTER INSTALLATION OF UNDERGROUND WIRING SHALL BE REINSTATED AND MADE GOOD BY THE CONTRACTOR.
- 8. LOCATE AND IDENTIFY ALL UNDERGROUND SERVICES BEFORE COMMENCING WORK.

EARTHING

- 1. EQUIPMENT AND ANTENNA MOUNTS SHALL BE EARTHED IN ACCORDANCE WITH THE EARTHING SPECIFICATION (OSD-030).
- 2. ALL EXTERIOR EARTH TAPE ELECTRODES SHALL BE COPPER BONDED HARDENED STEEL UNLESS OTHERWISE NOMINATED ON THE SITE DRAWINGS.
- 3. THE EARTHING SYSTEM SHALL BE CHECKED FOR CONTINUITY AND IMPEDANCE SHALL BE MEASURED AND A WRITTEN TEST REPORT PROVIDED.
- 4. EARTHING ELECTRODES SHALL BE INSTALLED AT A DEPTH OF NOT LESS THAN 3 METRES UNLESS NOTED OTHERWISE.

UNDERGROUND SERVICES

- 1. EXISTING SERVICES SHOWN ON SITE DRAWINGS IS REPRESENTATIVE OF AVAILABLE INFORMATION (OBTAINED FROM LOCAL AUTHORITIES) AND THE SITE SURVEY.
- 2. SERVICES INFORMATION SHALL BE READ IN CONJUNCTION WITH THE RELEVANT LOCAL AUTHORITIES DRAWINGS TO CONFIRM ACCURACY AND COMPLETENESS.
- 3. ADDITIONAL UNDOCUMENTED SERVICES MAY BE PRESENT ON SITE. FOR INFORMATION OF UTILITY UNDERGROUND SERVICES CALL 1100 'DIAL BEFORE YOU DIG'.
- 4. THE CONTRACTOR SHALL IDENTIFY AND CONFIRM THE LOCATION OF ALL RELEVANT UNDERGROUND SERVICES PRIOR TO COMMENCEMENT OF THE WORKS USING MANUAL POTHOLING OR OTHER APPROVED MEANS.

C	OCT 18	STRUCTURAL STEELWORKS NOTES AMENDED	HW	QG	JYW	BL	MVDL		
B	DEC 10	DATUM CHANGED TO MGA; ELECTRICAL REVISED	AA	DCL	DCL	MTA	NT		
A	NOV 08	ISSUED FOR CONSTRUCTION (REPLACES GSM-SPEC1)	CW	DCL	DCL	MTA	SN		
Rev	Date	Revision Details	Consultant	CAD	Designer	Verifier	Approver		



HUAWEI TECHNOLOGIES (AU) PTY LTD
ABN 49 103 793 800
SYDNEY
LEVEL 6 TOWER B 799 PACIFIC HIGHWAY
CHATSWOOD NSW 2067
TEL: +61 2 9928 3888 FAX: +61 2 9411 8533
MELBOURNE
LEVEL 24 499 COLLINS STREET
MELBOURNE VIC 3000
TEL: +61 3 8610 0600 FAX: +61 3 9621 1575



Client:

Project:

MOBILE NETWORK
AUSTRALIA
OPTUS STANDARD
DRAWING

Drawing Title:

STANDARD
CONSTRUCTION NOTES

Drawing Status:

FOR CONSTRUCTION

Drawing No.

OSD-100

Revision

C